Plant List

TREES

Symbol	Botanical Name	Common Name	Quantity	Size	Comments
Ab	*Abies balsamea*	Balsam Fir	6	7-8' ht.	BB
Ac	*Abies concolor*	White Fir	1	8-10' ht.	BB
Ak	*Abies koreana*	Korean Fir	1	7-8' ht.	BB
Am	*Amelanchier x grandiflora 'Autumn Brilliance'*	Autumn Brilliance Serviceberry	6	8-10' ht.	BB Multi-stemmed
Ar	*Acer rubrum 'October Glory'*	October Glory Red Maple	3	2-2.5" cal.	BB
Aa	*Acer saccharum 'Green Mountain'*	Green Mountain Sugar Maple	3	2-2.5" cal.	BB
Bn	*Betula nigra 'Heritage'*	Heritage River Birch	12	12-14' ht.	BB Multi-stemmed
Gt	*Gleditsia triancanthos inermis 'Halka'*	Halka Thornless Honeylocust	9	2-2.5" cal.	BB
Ham	*Hamamelis x intermedia "Arnold promise"*	Arnold Promise Witchhazel	1	7-8' ht.	BB Multi-stemmed
JcM	*Juniperus chinensis 'Mountbatten'*	Mountbatten Juniper	20	7-8' ht.	BB
Ls	*Liquidambar styraciflua*	American Sweetgum	13	2-2.5" cal.	BB
Lt	*Liriodendron tulipifera*	Tuliptree	7	2-2.5" cal.	BB
Mag	*Magnolia stellata 'Centennial'*	Centennial Star Magnolia	1	8-10' ht.	BB
Ns	*Nyssa sylvatica*	Black Tupelo	4	2-2.5" cal.	BB
Pa	*Picea abies*	Norway Spruce	38	8-10' ht.	BB
Pg	*Picea glauca*	White Spruce	29	7-8' ht.	BB
PoG	*Picea orientalis 'Gowdy'*	Gowdy Oriental Spruce	2	7-8' ht.	BB
Qa	*Quercus rubra*	Red Oak	13	2-2.5" cal.	BB
Sr	*Syringa reticulata 'Ivory Silk'*	Ivory Silk Japanese Tree Lilac	3	2-2.5" cal.	BB
Tc	*Tsuga canadensis*	Canadian Hemlock	10	8-10' ht.	BB
Th1	*Thuja plicata 'Green Giant'*	Green Giant Arborvitae	26	8-10' ht.	BB
Th2	*Thuja plicata 'Green Giant'*	Green Giant Arborvitae	16	10-12" ht.	BB
Tht	*Thuja occidentalis 'Techny'*	Techny Arborvitae	30	5-6' ht.	BB
Ua	*Ulmus americana 'Princeton'*	Princeton American Elm	10	2-2.5" cal.	BB

Seed Mix A

50% New England Wetland Plants – New England Conservation & Wildlife Mix
50% New England Wetland Plants – New England Wetmix

Lawn

Pennington Smart Seed Pro Tri- Fescue Mix, apply per manufacturer's recommendations

PERENNIALS, GROUNDCOVERS, VINES and ANNUALS

Symbol	Botanical Name	Common Name	Quantity	Size
Aj	*Ajuga reptans 'Burgundy Glow'*	Bugleweed	30	1qt
Ast	*Astilbe 'Fanal'*	Rubyred Astilbe	47	1 gal
Bap	*Baptisia australis*	False Blue Indigo	6	1 gal
Daff	*Narcissus 'Ice follies'*		90	1 gal
	Narcissus 'King Alfred'	King Alfred Daffodil	90	1 gal
	Narcissus 'Mount Hood'	Mount Hood Daffodil	90	1 gal
Day1	*Hemerocallis 'Big Time Happy'*	Big Time Happy Daylily	48	1 gal
Day2	*Hemerocallis 'Chicago Apache'*	Chicago Apache Daylily	48	1 gal
Day3	*Hemerocallis 'Country Melody'*	Country Melody Daylily	48	1 gal
Eup	*Eupatorium maculatum*	Joe-pye Weed	3	1 gal
F	*Dennstaedtia punctilloba*	Hay-scented Fern	189	1 gal
H1	*Hosta sieboldiana 'Elegans'*	Elegans Hosta	6	1 gal
H2	*Hosta 'Sugar Daddy'*	Sugar Daddy Hosta	2	1 gal
H3	*Hosta 'Stained Glass'*	Stained Glass Hosta	1	1 gal
Hak	*Hakonechloa macro 'Aureola'*	Yellow Hakone Grass	3	1 gal
Ir	*Iris sibirica 'Butter and Sugar'*	Yellow and White Siberian Iris	8	1 gal
	Iris sibirica 'Ceasar's Brother'	Dark Pansy Purple Siberian Iris	8	1 gal
Pec1	*Paeonia 'Felix Crousse'*	Felix Crousse Peony	5	1 gal
Pec2	*Paeonia 'Raspberry Sundae'*		5	1 gal
Rud	*Rudbeckia fulgida 'Goldsturm'*	Black-Eyed Susan	24	1 gal
Sal	*Salvia nemerosa 'Caradonna'*	Carradonna Sage	9	1 gal
Sed	*Sedum 'Autumn Joy'*	Autumn Joy Sedum	4	1 gal
Vm	*Vinca minor 'Bowles'*	Bowles Periwinkle	760	2" pots

SHRUBS

Symbol	Botanical Name	Common Name	Quantity	Size	Min Height	Min Width	Comments
Ap1	*Azalea kiusianum 'Best Pink'*	Best Pink Azalea	2	2gal.			
For	*Forsythia x intermedia 'Gold Tide'*	Dwarf Forsythia	19	3 gal.	12"	18"	
HLL	*Hydrangea paniculata 'Little Lime'*	Little Lime Hydrangea	8	3 gal	24"	24"	BB
Hs	*Hibiscus syriacus 'Blue Satin'*	Blue Satin Rose-of -Sharon	1	5-6' ht.			BB - Full
HyA	*Hydrangea arborescens 'Annabelle'*	Annabelle Hydrangea	22	5 gal.	24"	24"	
HyE	*Hydrangea macrophylla 'Endless Summer'*	Endless Summer Hydrangea	6	3 gal.			
Ig5	*Ilex glabra 'Shamrock'*	Shamrock Inkberry		3 gal.			
InCG	*Ilex meserve 'China Girl'*	China Girl Holly		3 gal	24"	24"	
InCB	*Ilex meserve 'China Boy'*	China Boy Holly		5 gal.	24"	24"	BB
Rh1	*Rhododendron 'Chionoides'*	Chionoides Rhododendron		2-2.5' ht.			BB
Rh2	*Rhododendron 'Nova Zembla'*	Nova Zembla Rhododendron		2-2.5' ht.			
Ra	*Rhus aromatica 'Grow-Low'*	Grow Low Sumac	93	3 gal	12"	18"	
RoK	*Rosa 'Knockout'*	Knockout Double Red Rose	16	3 gal.	12"	18"	BB
RhS	*Rhododendron 'Scintillation'*	Scintillation Rhododendron	21	2-2.5' ht.			
Sp	*Spiirea x bumalda 'Anthony Waterer'*	Anthony Waterer Spirea	42	3 gal	18"	18"	
SpG	*Spiirea x bumalda 'Goldflame'*	Goldflame Spirea	6	3 gal	18"	18"	
Syr	*Syringa vulgaris*	Common Lilac		2.5-3' ht.			BB
Syj	*Syringa 'Charles Joy'*	Charles Joy Lilac	32	5-6' ht.			BB
SyP	*Syringa meyeri 'Palibin'*	Dwarf Korean Lilac	5	3-4' ht.			BB
TaE	*Taxus media 'Ever-Low'*	Ever-Low Yew	6	2-2.5' Ht.	2'	2.5'	BB
Tt	*Taxus media 'Taunton'*	Taunton Yew	33	2-2.5' ht.	2'	2.5'	BB
VpT	*Viburnum plicatum tomentosum 'Mariesii'*	Mariie's Doublefile Viburnum	12	3-4' ht.			BB

Landscape Notes

1. Design is based on drawings by Jones & Beach dated July 3, 2018 and may require adjustment due to actual field conditions.
2. The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and protect the site and adjacent.
3. Erosion Control shall be in place prior to construction.
4. Erosion Control to consist of Hay Bales and Erosion Control Fabric shall be staked in place between the work and Water bodies, Wetlands and/or drainage ways prior to any construction.
5. The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any discrepancies between the plan and field conditions prior to construction or installation.
6. It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation. A graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is incorrect, the Landscape Architect or Client's Representative shall be notified immediately in writing.
7. Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line at a minimum and shall include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, branches, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on those areas within the drip line(s) of the tree(s). Do not store any refuse or construction materials or portable vehicles in the protection areas.
8. Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the Contractor.
9. The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction. Call Dig Safely at 1-888-DIG-SAFE.
10. The Contractor shall procure any required permits prior to construction.
11. Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates, macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall provide Landscape Architect with test results and recommendations for any amendments. Do not place any loam until recommendations have been made and approved. Amend planting to Rates. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement.
12. Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a condition is not reported to the landscape architect or owner's representative prior to being addressed by the representative immediately, they may be responsible for the labor and materials associated with correcting the problem.
13. The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical nomenclature of standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurseries, Inc. in the latest edition of *American Standard of Nursery Stock*, American Standards Institute, Inc. 230 Southern Building, Washington, D.C. 20005.
14. A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event of discrepancy between the quantities shown on the drawings and in the plant materials list, the planting plans shall govern.
15. All plants shall be legibly tagged with proper botanical name.
16. The Contractor shall guarantee all plants for not less than one year from time of acceptance.
17. Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and reject any plant material at any time during the progress of the work if it does not meet specifications. A sample of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard for all plants of the same species used in this work.
18. No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason.
19. All landscaping shall be provided with either of the following
    a. An automatic irrigation system
    b. An outside hose attachment within 150 feet.
20. If an automatic irrigation system is installed, all irrigation valve boxes shall be located within planting bed areas.
21. The contractor is responsible for all plant material from the time their work commences until final acceptance. This includes but is not limited to maintaining all plants in good condition, the security of the plant material once delivered to the site, and watering all plants to the extent recommended by nurseries before, during and after planting. It is the contractor's responsibility to provide water from off site, should it not be available on site.
22. All disturbed areas will be dressed with 6" of topsoil and planted as noted on the plans or seeded except plant beds. Plant beds shall be prepared to a depth of 18" with the top 12" being topsoil.
23. Trees, ground cover, and shrubs shall be mulched with hardwood bark to a depth of 2" with one-year-old, well-composted, shredded native hardwood bark. Mulch for trees is 4' in length and 12" in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length. Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be black.
24. In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied mulch) over the root ball of any plant.
25. Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a height of 8' to allow clear and safe passage of vehicles and pedestrians under tree canopy.
26. Snow shall be stored a minimum of 5' from shrubs and trunks of trees.
27. Landscape Architect is not responsible for the means and methods of the contractor.

woodburn & company
LANDSCAPE ARCHITECTURE
103 Kent Place Newmarket, New Hampshire Phone: 603.658.5949

New London Place
LANDSCAPE PLAN RENDERING
County Road & Parkside Road New London, NH

Drawn By:	VM
Checked By:	RW
Scale:	1" = 40' - 0"
Date:	July 3, 2018
Revisions:	

L-1A

NOT IN SET

0 10 20 40 80

© 2018 Woodburn & Company Landscape Architecture, LLC